

2018 Public Works Road Projects

Type of Work	Road/Street	From	To	Total Length	Work Required
Reconstruction	Meach Road	Asseltine Road	County Road 41	3.0km	Pre-engineering, survey costs
Reconstruction	Road 1	County Road 8	Highway 33	2.3km	Pulverize and Double Surface Treatment (DST)
Reconstruction	Dundas St	Centre St	Adelphi St	0.3km	Electrical and Lighting
Tar & Chip	Bridge Street	900 Bridge St W	.5km W 900 Bridge St	0.5km	Pulverize .5km West lane, reshape and DST
Tar & Chip	PW Entrance	County Road 2	PW Yard	0.3km	Grade and DST
Tar & Chip	Pine Grove Road	County Road 12	Cooks Road	0.5km	Pulverize, grade and DST
Paving	Goodyear Road	County Road 41	3km East to Boundary	3.0km	Pulverize, Pave 60mm Base and 40mm Top
Paving	Kellwood Crescent	0.2km N of Richmond Blvd	Richmond Blvd	0.46km	Pulverize, Pave 50mm HL8 Base and 40mm HL3 Top
Paving	Plesant Drive	County Road 41 South	County Road 11	0.64km	Pulverize, Pave 50mm HL8 Base and 40mm HL3 Top
Paving	Market Sq	Walk Behind Town Hall and 12 Market Sq			Pave walk behind Town Hall and repave 12 Market Sq